


**CITY OF LOS ALTOS**  
**Community Development Department**  
**Building Division**



**POOL DEMOLITION REQUIREMENTS**

REVISED: March 2011

**\*\*PROVIDE (2) COPIES OF SITE PLAN SHOWING APPROXIMATE  
LOCATION (IN LINEAL FEET) OF SWIMMING POOL ON LOT\*\***

1. Obtain a Demolition Permit. **PERMIT MUST BE KEPT AT JOB SITE AND AVAILABLE TO INSPECTOR.** This form shall remain attached to the "Job Inspection Card."
2. Drain pool to sanitary sewer. Do not drain to street gutters or storm water systems.
3. Break down pool wall 30" to 36" below grade & remove debris. Do not leave concrete debris in pool.
4. Breakout concrete deck around pool & remove debris.
5. Cut and remove pool equipment, gas and water. Electrical lines to be removed from pool and sub panel. Label panel appropriately for spare breaker.
6. Puncture holes in pool floor three feet on center each way.
7. Breakout a 4' x 4' hole at lowest point (deep end).
8. Remove all debris from site. Do not stockpile debris in street. If using a dumpster to container debris, it must be supplied by **Mission Trail, (650) 473-1400 or mission trail.com**
9. **(650) 473-1400 or mission trail.com**
10. Do not stockpile gravel or fill dirt in street without first obtaining an encroachment permit from **City of Los Altos Engineering Division, (650) 947-2780**
11. **CALL FOR INSPECTION.**
12. Cover pool bottom with 6" to 8" of drain rock.
13. Install felt drain fabric over drain rock.
14. Fill pool area in 6" to 12" lifts and compact to 90%.
15. Roll-in, do not compact, last 12" of quality fill dirt.
16. Clean up area and access.
17. **CALL FOR REQUIRED FINAL INSPECTION.**