# **GUIDANCE TECHNICAL SPECIFICATION**

These guidance specifications are general city requirements. They shall be incorporated into project specific technical specifications. The city utilizes the latest edition of the California Department of Transportation Standard Specifications and the American Public Works Association Standard Specifications for Public Works for Construction (Green Book).

## **SECTION 1 CLEARING AND GRUBBING**

### 1-01 GENERAL

This work shall consist of clearing and grubbing the area within the limits of work of all rubbish, debris, vegetative material and objectionable material as deemed necessary to perform the work or as otherwise specified on the plans. Clearing and grubbing shall conform to the requirements of Section 15, "Existing Highway Facilities," and Section 16, "Clearing and Grubbing," of the Caltrans Specifications, except as modified herein.

#### 1-02 MATERIALS

None.

### 1-03 CONSTRUCTION

The Contractor should examine the work site and verify existing conditions prior to commencement of work.

The areas requiring clearing and grubbing shall be graded to a relatively smooth final grade. All deleterious material, rocks, paper and other objectionable material shall be removed. The Contractor shall separate asphalt concrete and portland cement concrete improvements which are to remain from those to be removed by sawcutting along the conform line.

Spoils resulting from clearing and grubbing shall be removed from the site and properly disposed of, by the Contractor.